



BREAK OUT & REMOVE EXISTING CROSSOVER WATERTABLE & REPLACE WITH NEW KERB & WATERTABLE TO MATCH EXISTING.

SAW CUT EXISTING BITUMEN AS REQUIRED FOR INSTALLATION OF NEW CROSSOVER & REMOVAL OF EXISTING CROSSOVER. MAKE GOOD EXISTING BASE COURSE & BITUMEN WEARING SURFACE TO MATCH EXISTING.

BREAK OUT & REMOVE EXISTING KERB & WATERTABLE. INSTALL NEW CONCRETE CROSSOVER TO COUNCIL REQUIREMENTS.

**LEGEND**

- EXISTING SPOT LEVEL
- EXISTING CONTOUR LEVEL
- EXISTING TREE LOCATION
- EXISTING STORMWATER PIPE
- EXISTING TREE TO BE REMOVED
- EXISTING SHRUBS TO BE REMOVED
- NEW FINISHED SPOT LEVEL
- NEW STORMWATER PIPE INVERT LEVEL
- NEW SWALE INVERT LEVEL
- NEW DIRECTION OF FALL
- NEW STORMWATER PIPE
- DENOTES BOREHOLE LOCATION
- DENOTES 100 HIGH KERB ONLY
- DENOTES 100 HIGH KERB & WATERTABLE
- DENOTES 150 HIGH KERB ONLY
- DENOTES 150 HIGH KERB & WATERTABLE
- DENOTES EXTENT OF 160mm THICK CONCRETE PAVING. REFER DRAWING 99/35-SW03 FOR DETAILS.
- DENOTES EXTENT OF 30mm THICK HOTMIX PAVING. REFER DRAWING 99/35-SW03 FOR DETAILS.
- DENOTES EXTENT OF 40mm THICK BRICK/BLOCK PAVING. REFER DRAWING 99/35-SW03 FOR DETAILS.
- DENOTES EXTENT OF 160mm THICK CONCRETE COUNCIL CROSSOVER. REFER DRAWING 99/35-SW03 FOR DETAILS.

9.16 TBM - BOLT ON STOBIE 350 A. G. L.

- 1 MAY 2000

FOR CONCRETE PAVING JOINTING REQUIREMENTS REFER DRAWINGS 99/35-SW03 & 99/35-SW04

Issue	Details	Date	Int

**CC&L Consultants**

CC&L Consultants Pty Ltd AGN 065 336 683  
 Consulting Structural & Civil Engineers Ph (08) 8363 0077  
 Suite 7, 15 Fullarton Road KENT TOWN SA 5067 Fax (08) 8363 0632



Telephone: (08) 8332 4455  
 Facsimile: (08) 8332 4466

**PROPOSED DEVELOPMENT FOR REDOX CHEMICALS PTY LTD CAVAN ROAD DRY CREEK**

**SOUTHERN SITEWORKS PLAN**

Scale	1:250	Drawing Number	99/35-SW02	Issue
Date	JAN '00			
Drawn	BSW			
22/2/00 2:47 PM		FILE NAME: 99035-SW02		